



## AUTOMATIC BALE STACKING SYSTEM

### HIGH DENSITY BALE STORAGE

A ceiling crane takes the bales from the press, transfers them to interim storage and loads the bales onto palettes. The automatically operating, above floor crane system enables the temporary storage of bales of very high density. Up to three bales can be stacked on one palette. The crane transports bales of a size between 700 x 500 mm and 1000 x 750 mm and up to 1000 kilos in weight.

PRODUCT NEWS

